

# The Report Card



# The assignment


- Develop and test stream corridor ecosystem rehabilitation practices that
  - ◆ Are applicable at the **landscape scale**
  - ◆ Provide acceptable levels of **stability** and **conveyance**
  - ◆ Are **low cost** and **low maintenance** (feasible for landowner implementation)
  - ◆ Work with geomorphic processes to produce natural **forms** and **functions**

# The site

## Modified reach

- 4<sup>th</sup>-order stream
- Watershed area = 37 km<sup>2</sup>
- Maximum relief ~ 65 m
- Mixed cover land use
- Test bed for many types of research
- Cooperating action agencies provided construction funds, but *no special research funding.*

Little Topashaw Creek Watershed



## A very unstable environment



Sediment yield dominated (~85% of total) by products of channel bed and bank erosion.

# Categories of research

## ■ Process studies--2

Grades are on effectiveness of  
measures—not on science or  
scientists!!

success--J

Process studies—no grade assigned

# Geomorphology

- Watershed characterization
- Knickpoint migration rates  
(up to 12 m/yr)

- Cohesive bed and bank erosion

- Real-time process—No Grade  
downstream 3/4 aggrading,  
upstream 1/4 degrading



# Subsurface erosion

- Seepage flow and sediment concentrations were measured *in situ* at eight locations


- Sediment concentrations as high as  $660 \text{ g L}^{-1}$

- Foundation for laboratory lysimeter

- Results compared to ARS Bank Stability Model simulations

Process—No Grade





# Management practices for channel erosion and habitat rehabilitation

# Bank stabilization using pumps

- Reduced pore water pressure
- Retreat rate lowered by factor of 2 over




two-year period

■ No mass failures

■ Safety factor increased

## Effectiveness of pumps—B-

■ Maintenance issues



## Structure status

	Jan-01	May-01	Jan-02	Mar-02	Aug-02	Jun-03
intact	69	68	50	43	34	25
destroyed	3	4	15	22	22	21
Grand Total	72	72	72	72	72	72

Effectiveness of large wood structures—D

# Willow cuttings for bank stabilization



- 4000 willow cuttings planted on bars and banks

- Performance of presoaked and unsoaked cuttings showed positive effects of soaking on survival and growth

- **Effectiveness of willows—F**  
governed by soil texture and depth to water table


- Three-year survival < 10%!


# Riparian gully stabilization using switchgrass hedges

- Hedges planted at 0.5-m vertical intervals
- Tested using pumped flows and natural runoff
- Main body of gully was stabilized

Effectiveness of hedges—D+

progressing from streambed into gullies





Indicators of overall project success

# Water quality

- Selected nutrients (Total N, PO<sub>4</sub>) often exceeded proposed TMDL criteria, suggesting adjustment needed for regional characteristics

- Many pesticides were detected in runoff events following applications
- Pesticide detections and concentrations correlated with runoff events following applications
- Analysis of effects of rehabilitation still pending

## Water quality effects of project--I



*Cooper, Smith, Lizotte*

# Hydraulic retention

- Mean velocity reduced 40 % relative to downstream

untreated reach eight months after construction

Overall retention 100%

## Effects of project on retention--C

large wood ( $F_{med}$ )

Hyporheic storage less than 0.5% of total storage




Rhodamine Dye Concentration vs Time after




# Organic carbon in bed

- Surficial (top 10 cm) bed sediments sampled immediately before and 3 yr after rehabilitation
- OC levels were about half the reference sites and were unchanged by rehabilitation



## Effects on bed carbon--F




# Sediment retention and stabilization

- Repeated channel surveys, acoustic Doppler loggers, and a two-dimensional numerical model all showed that high flow velocities were retarded along concave bank toes by LW structures, promoting

## Effects on erosion control—F

- Eventual failure of LW structures allowed deposited sediments to be scoured away.



# Aquatic macroinvertebrates

- Large increases in abundance of “desirable” types
- Increased biodiversity



- These increases occurred in treated and untreated reaches
- Major shifts in community composition in a reach
- Final analysis still pending

**Effects on inverts—I**


*Cooper, Testa*

# Fish and their habitats

- Field data and numerical modeling indicated initial improvements in habitat quality due to LW addition
- Longer-term habitat effects were modest—mostly just an increase in LW density
- Number of fish species doubled
- Species composition shifted to be more typical of less-degraded reference site
- Some similar changes occurred in the untreated reach downstream



## Effects on fish—C



*Knight, Wu, He*

# Lessons learned



- Multidisciplinary watershed scale research is a worthy endeavor, providing (but not replacing) more basic, controlled laboratory and plot-scale studies
- Watershed research benefits from synergy of many types of investigation in the same locale
- We need to rethink control of concentrated flow erosion
- Ecological restoration, particularly in agricultural watersheds, is a daunting task